**Greater Cleveland Regional Transit Authority** 



# E. 79<sup>th</sup> Street Light Rail Station Conceptual Design

Operational Planning & Infrastructure Committee

January 9, 2024


### **Project Overview**

- East 79th Street Light Rail Station was rebuilt in the early 1980's and serves GCRTA's Blue and Green light rail lines and has reached the end of its useful life
- Primary purpose of this project:
  - Rehabilitate the station and bring it into ADA compliance.
  - Improve connections into the neighborhood and provide
    Transit Oriented Development opportunities



#### **Transit Oriented Development**






Images from the East 79<sup>th</sup> Street Corridor Study showing the potential for Transit Oriented Development Greater Cleveland Regional Transit Authority The E. 79<sup>th</sup> Light Rail Station offers an opportunity to attract high-quality, mixeduse development

- Benefits existing residents and workers
- Attracts new residents, new jobs and new opportunities to the area.



### **Environmental Justice**



- E. 79<sup>th</sup> Street Light Rail Station is located is an area of Environmental Justice concern
  - Minority Population is > 30.73%
  - Population below Poverty Level > 13.47%
  - In 2023 The GCRTA has invested \$18.6 million on project in EJ zones.
    - This accounts for 77% of money spent on major projects




Greater Cleveland Regional Transit Authority 💳

**GCRTA** Capital Projects

#### **Opportunity Corridor Investments**

Opportunity Corridor Zone



	Projects	Investment
1	East 79 <sup>th</sup> Street Red Line Station	\$6,726,718
2	Wayside Signal Design – East 79	\$250,000
	to Shaker Square	
2	East 79 <sup>th</sup> Street Light Rail Station	\$10,000,000
3	Consolidated Train Dispatch	\$3,575,474
	System Replacement	
4	East 75 <sup>th</sup> Light Rail Interlocking	\$3,531,000
_	Reconstruction	
5	Redline Fiber Optic Upgrade – East 55 <sup>th</sup>	
1	Redline Fiber Optic Upgrade – East 79 <sup>th</sup>	\$6,115,000
5	Redline Fiber Optic Upgrade – East 105 <sup>th</sup>	



#### **Project Site Map**



- The station is elevated above the street level, accessed by a single stairway off E. 79<sup>th</sup> St.
- South of the station is Hillside Community Park



## **Design Elements/ Existing Conditions**

- The entrance is to serve as waiting environment for the GCRTA No. 2 bus route
- Provide ADA compliant crosswalk
- Provide provisions for the installation of a bus shelter on the east side of E. 79th Street



**Existing Steet View:** 





### **Design Elements/ Existing Conditions**

- Provided covered access, via stair/ramp, from E. 79th Street to the station's platform
- Provide access between Hillside Community Park and the Station



**Existing Station Entrance:** 



Existing Sidewalk Condition:



**Existing Stairs:** 



### **Design Elements/ Existing Conditions**

- Provide two new light rail platforms for the eastbound and westbound tracks
- Provide ADA compliant pedestrian grade crossing for access between platforms
  - Trackwork was replaced as part of the Light Rail Track Rehabilitation Program in 2021




Existing Westbound Platform:




#### Site Analysis



























#### **Conceptual Design – Site Plan**







#### **Conceptual Design – Overall Site Plan**













































### **Project Budget/ Schedule**

- Construction Estimate: \$8,100,000
  - Funded through All Stations Accessibility Program (ASAP) Grant
- Anticipated Project Schedule:
  - Design: August 2023 to October 2024
    - 420 days from NTP
  - Bidding: November 2024 to February 2025
  - Construction: March 2025 to September 2026
    - Approximately 18 Months



### **Community and Stakeholder**

- Stakeholders Involvement:
  - Conceptual Design Workshop: October 25, 2023
    - GCRTA User Departments
    - City of Cleveland
    - Burten Bell Carr Development Inc.
  - Public Meeting:
    - Working to schedule in January
  - GCRTA Community Advisory Committee
    - Working to schedule in January



#### Questions?

